

## IPC 9521 | SUBMITTAL

**File No:** 90.581N  
**Date:** DEC. 15, 2014  
**Supersedes:** NEW  
**Date:** NEW

Job: \_\_\_\_\_ Representative: \_\_\_\_\_  
 \_\_\_\_\_ Ordered by: \_\_\_\_\_ Date: \_\_\_\_\_  
 Engineer: \_\_\_\_\_ Submitted by: \_\_\_\_\_ Date: \_\_\_\_\_  
 Contractor: \_\_\_\_\_ Approved by: \_\_\_\_\_ Date: \_\_\_\_\_

### CONFIGURATION

SYSTEM	COOLING TOWERS** QUANTITY	PRIMARY PUMP SPEED CONTROL	FOR ZONE(S)
Quantity of water cooled chillers	<input type="checkbox"/> 1 <input type="checkbox"/> 2	<input type="checkbox"/> Sensorless	1
	<input type="checkbox"/> 3	<input type="checkbox"/> Local Plant dP sensor	
	<input type="checkbox"/> 4	<input type="checkbox"/> Zone differential pressure sensor(s)	1 to 5
	<input type="checkbox"/> 5	<input type="checkbox"/> Zone return temperature sensor(s)	
Capacity per chiller*	Tons		
Number of zones	(Specify 1 to 5)		

\* All chillers, pumps on each set & cooling towers have to be of identical capacity  
 \*\* Only headered cooling towers are allowed. 1 speed signal/VFD is considered per tower

SYSTEM LAYOUT	CONFIGURATION	OPERATION	QUANTITY OF CHW PRIMARY PUMPS		
Primary CHW pumps	<input type="checkbox"/> Single	<input type="checkbox"/> Headered	<input type="checkbox"/> Parallel	<input type="checkbox"/> Duty pumps = number of chillers	(1 to 5) Duty + 0 Standby
			<input type="checkbox"/> Standby	<input type="checkbox"/> Duty pumps = number of chillers* + 1 Standby pump	(1 to 4) Duty + 1 Standby
		<input type="checkbox"/> Dedicated	<input type="checkbox"/> Parallel	<input type="checkbox"/> Duty pumps = number of chillers	(1 to 5) Duty + 0 Standby
			<input type="checkbox"/> Standby	<input type="checkbox"/> Duty pumps = number of chillers + Standby pumps = number of chillers	(1 to 5) Duty + (1 to 5) Standby**
	<input type="checkbox"/> DualArm <input type="checkbox"/> Twin	<input type="checkbox"/> Dedicated	<input type="checkbox"/> Parallel	<input type="checkbox"/> Duty pumps = number of chillers	(1 to 5)***

\* Up to 4 chillers systems  
 \*\* Equal number of duty and standby pumps  
 \*\*\* 1 DualArm = 2 rotating assembly (considered Duty/Duty)  
     1 Twin = 2 rotating assembly (considered Duty/Standby)

SYSTEM LAYOUT	CONFIGURATION		OPERATION	QUANTITY OF CHW PRIMARY PUMPS	
Condenser cw pumps	<input type="checkbox"/> Single	<input type="checkbox"/> Headered	<input type="checkbox"/> Parallel	<input type="checkbox"/> Duty pumps = number of chillers	(1 to 5) Duty + 0 Standby
			<input type="checkbox"/> Standby	<input type="checkbox"/> Duty pumps = number of chillers* + 1 Standby pump	(1 to 4) Duty + 1 Standby
		<input type="checkbox"/> Dedicated	<input type="checkbox"/> Parallel	<input type="checkbox"/> Duty pumps = number of chillers	(1 to 5) Duty + 0 Standby
			<input type="checkbox"/> Standby	<input type="checkbox"/> Duty pumps = number of chillers + Standby pumps = number of chillers	(1 to 5) Duty + (1 to 5) Standby**
	<input type="checkbox"/> DualArm <input type="checkbox"/> Twin	<input type="checkbox"/> Dedicated	<input type="checkbox"/> Parallel	<input type="checkbox"/> Duty pumps = number of chillers	(1 to 5) Duty + 0 Standby

\* Up to 4 chillers systems

\*\* Equal number of duty and standby pumps

**STANDARD FUNCTIONALITY AND CONSTRUCTION**

The Armstrong IPC 9521 is a pre-programmed control system, designed for the automation of a water cooled variable primary chiller plant. It includes:

- 2 panels mounted on a wall rack
- The master panel has a large-sized (10.4") touch-screen operator interface (not to be directly exposed to sunlight)
- On-screen menu driven operator interface manual or automatic system control (H-O-A selection)
- Multi-color schematic active display of mechanical room hydraulic circuit indicating operating status
- Remote or local start/stop mode of operation
- Three field and two factory levels password security
- Secure front cabinet door with lock and key
- Alarm and event logging of 2000 events
- Data trending available on a csv file
- Internal circuit breaker protection
- Automatic or manual pump alternation
- **Alarms:** ① controller communication alarm, ② sensor alarm, ③ general system alarm, ④ Individual equipment (chiller, pumps, tower fans, valves, auxiliary equipment) alarm
- Standard Modbus RTU communication between IPC controller and VFD's (pumps and towers)
- Logic outputs for chiller 2-way automatic ON/OFF isolation valves
- Logic output for chiller 2-way automatic modulating bypass valve
- Digital inputs for pump differential pressure switches on all variable speed primary pumps
- Output for remote alarm/horn signal
- Input for silencing of remote alarm/horn
- Automatic sequencing of chillers
- Sequencing, isolation valve, and modulating control for chillers in a variable primary flow application
- Pump speed, cooling valves and bypass valve PID control loop, adjustable
- Parallel Sensorless™ primary pumps control mode with best efficiency point staging.
- Cooling valves control mode (ASHRAE 90.1)
- Separate operating status display of primary and secondary pump status, pump speed(s) and drive status
- Separate operating status display of chiller status, demand limit, power, temperatures
- Separate operating status display of tower fan, tower fan speed(s) and drive status
- Separate operating status display of isolation and bypass valves
- Separate input screens for; set points, differential pressure sensors, flow and kW monitors
- Separate status display screens for; pump status, zone status, system status, plant status
- **Power supply:** 100V-240V AC/1 phase/50-60 Hz
- Ambient air Temperature for operation range : (0 to 45°C)
- Ambient air temperature for storage range : (0 to 60°C)
- Relative humidity : (10...85 %) Non Condensing
- Operating altitude 2000 m


**OPTIONAL FEATURES AND DIMENSIONS**

CHILLER COMMUNICATION		DIMENSIONS AND WEIGHTS				
		LENGTH	HEIGHT	DEPTH	WEIGHT	ENCLOSURE
Interface OR	<input type="checkbox"/> Modbus RTU <input type="checkbox"/> BACnet™ MS/TP	2100 (82.70)	1100 (43.30)	321 (12.60)	70 (154)	<input type="checkbox"/> IP54
	<input type="checkbox"/> BACnet™ IP <input type="checkbox"/> LonWorks®					
Hardwired (Output 0-10V)		2541 (100.00)	1078 (42.40)	395 (15.60)	80 (176)	<input type="checkbox"/> IP55*
Hardwired (Output 4-20 mA)	<input type="checkbox"/>	2100 (82.70)	1200 (47.20)	321 (12.60)	75 (165)	<input type="checkbox"/> IP54
	<input type="checkbox"/>	2541 (100.00)	1228 (48.30)	395 (15.60)	90 (198)	<input type="checkbox"/> IP55*

**Notes:**

- Dimensions in mm (inches) Weights in kg (lbs)
- Weights are approximate

\*Recommended for outdoor application.



**OPTIONS**

- ECO\*PULSE embedded intelligence (diagnostic service available on a subscription basis)
- Export crating
- On-site start up by 1 trained Armstrong service provider.

**BAS COMMUNICATION**

- Not required
- Modbus RTU
- Modbus TCP
- BACnet™ MS/TP
- BACnet™ IP
- LonWorks®

4

INSTRUMENTATION (FOR THE PUMP CONTROL)	TOTAL QUANTITY	FOR PRIMARY PUMP SPEED CONTROL			
		SENSORLESS	LOCAL PLANT DP	ZONE DP	ZONE RETURN TEMP
<input type="checkbox"/> Zone dP sensors		N/A	N/A	= qty of zones	N/A
<input type="checkbox"/> Zone return temperature sensors		N/A	N/A	N/A	= qty of zones
<input type="checkbox"/> Pump head dP sensor		N/A	1*	N/A	N/A
<input type="checkbox"/> Plant dP sensor with package		N/A	1	N/A	N/A

\* Not required with Design Envelope pumps

INSTRUMENTATION (FOR THE SYSTEM)	TOTAL QUANTITY
<input type="checkbox"/> Primary flow sensor	1
<input type="checkbox"/> Primary supply and return temperature sensors	2
<input type="checkbox"/> Chiller kW sensors*	= qty of chillers
<input type="checkbox"/> Condenser temperature sensors	2
<input type="checkbox"/> Condenser flow sensor	1
<input type="checkbox"/> Outside air temperature & humidity sensor	1

\* Optional if each chiller already has an integrated kW reading

TORONTO

+1 416 755 2291

BUFFALO

+1 716 693 8813

BIRMINGHAM

+44 (0) 8444 145 145

MANCHESTER

+44 (0) 8444 145 145

BANGALORE

+91 (0) 80 4906 3555

SHANGHAI

+86 21 3756 6696